



# Mai Municipality

## Office of Municipal Executive

Phone : ०२७-४१२२२२

Website : maimun.gov.np

Email: mainagarpalika@gmail.com

Facebook Page : facebook.com/maimun2

L.N. 2077/078

D.N.



Province 1

Date: 2078/02/21

### Subject: Notice for Bid Addendum

This is to notify all the concerned bidders that addendum has been issued for the NCB title "Construction of Mai Eco Tourism City Development Project" published on 2078/01/26 through "<http://bolpatra.gov.np/egp>". The Addendum can be downloaded from PPMO's e-procurement portal <http://bolpatra.gov.np/egp>.

(Bishnu Kumar Theguwa)

Chief Administrative Officer

**Bishnu Kumar Theguwa**  
Chief Administrative Officer



# **Bid Addendum Report**

## **Mai Municipality, Danabari, Ilam**

Mai Municipality, Danabari, Ilam  
Danabari  
Danabari, Ilam  
Province One  
Ilam  
Nepal

**Addendum No: 1**

**Published On: 04-06-2021 09:00**

**Invitation No: MM/NCB/WORKS/NOTICE/14/077/78**

**Dated On: 09-05-2021 00:00**

Following changes are made in the bid document



### Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2021-06-04 09:00:00

*Sim*  
असीम माण्डारी  
इन्जिनियर

*Bishnu Kumar Theguwa*  
Bishnu Kumar Theguwa  
Chief Administrative Officer

## Chapter: Bill of Quantities



### 1 Provisional Sum

#### Procurement Item Details

SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)
1	(a) Insurance premium for the work, plant and materials damage for contract work for all risk including Riot, Strike, Damage, Malicious damage and Terrorism for contract work of 1.5 years + 1 year Maintenance period., (b) Insurance Premium for construction equipments and machines with value of Rs 500,000.00 for 1.5 years., (c) Insurance Premium for property except the works, plants, Materials and equipment in connection with contract with Value of Rs. 10,00,000 for 1.5 years., (d) Insurance premium for the insurance of employees Staff ( 3 Nos ) and Contractor's staff and others (3 Nos ) Rs. 500,000.00 per person for Unnamed 10 persons with unlimited number of occurrences for 1.5 years	Ps	1	300000	300000

### 2 Construction work

#### 2.1 Works for complete or part construction and civil engineering work

##### 2.1.1 Engineering works and construction works

#### Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Fixing at site a Display Board ( 750 x 1000 mm ) with project name clearly written in Plain sheet in wooden frame all complete.	Ls	1.0			
2	Diversion of river flow for excavation of Retaining wall and other works including dewatering and construction of coffer dam	Ls	1.0			
3	Earth work in excavation of hard soil, soft clay, silty & wet soils all condition as per instruction of site engineer all complete. Disposal works upto 10m and transportation upto 1.5 m	cum.	2880.91			
4	Providing, laying, compacting and curing plain cement concrete M10 (1:3:6) in foundation bed with cement, sand and well graded crushed stone aggregate finishing to approved level, lines and dimensions all complete as per drawings, specification. transportation upto 30m.	cum.	181.73			
5	Providing & laying boulder stone soling in foundation & floor all complete as per instruction of the site engineer.	Cum.	317.04			

*असिम मण्डारी*  
असिम मण्डारी  
असिम मण्डारी

*Bishu Kumar Theguwa*  
Bishu Kumar Theguwa  
Chief Administrative Officer



Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
6	Providing & laying 1st class local chimney made brickwork in 1:4 C/S mortar in superstructure in ground floor in perfect line level finish including wetting the bricks, racking the joints and curing the work for at least 7 days as per specification, drawings & instructions of the site engineer all complete. transportation upto 30m.	cum.	252.24			
7	Providing, mixing with mixer machine, laying, compacting with vibrator and curing plain cement concrete M20 (1:1.5:3) using ordinary portland cement (OPC) for foundation, coloumn, slab, beams, tie beam Lintel Sill and all kinds of R.C. C. works with cement sand and crushed stone aggregate 20mm down finishing to approved level lines and dimensions all complete as per drawings, specifications and instruction of the site engineer. transportation upto 30m.	cum.	429.32			
8	Providing Reinforcement bars (Grade 415 or above) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation column, beam, wall, stair, slab in all R.C. C. works as per specification, drawing & instruction of site engineer and transportation upto 30m.	kg	45932.66			
9	18mm plywood formwork including necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for Slab/Beam etc. complete work.	Sqm.	3464.72			
10	Providing and fixing Seasoned Sal wood work for Chaukhat Frame of Doors all complete according to the specification of site engineer all complete	cum.	1.94			
11	Providing and fixing 38mm thick sal wood fully panelled door shutter with jack planes, fixing in position in perfect line and level with 150mm size 3 no of hinges, heavy quality aluminium tower bolt 150mm long, one number mortice lock high quality, all complete	Sqm.	35.62			

*Asim*

असीम भण्डारी  
इन्जिनियर

*Bishnu Kumar Theguwa*

Bishnu Kumar Theguwa  
Chief Administrative Officer



Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
12	Making and fitting Sal Wood glazed window shutter of 38*75 mm frame and 4mm thick glass fully glazed shutter including all necessary hardware fitting all Complete.	Sqm.	37.73			
13	Earthworks in filling with river bed materials for construction of embankment including watering and well compaction in specified layer including all lead and lift.	cum.	31020.49			
14	Providing and laying 38mm thick screeding with M15 concrete & 3mm thick punning works all complete as per instruction of site engineer all complete.	Sqm.	561.36			
15	Providing, laying & curing 12.5 mm thick cement sand (1:4) Plaster on ceiling and walls to perfect plumb, lines & level all complete as per design drawings, specifications and instruction of the site engineer all complete.	Sqm.	2546.68			
16	Supplying and laying 2 coats of plastic emulsion paint over one coat of primer onl walls of uniform finishing all complete as per instruction of site engineer all complete	Sqm.	1305.85			
17	Two coat readymade enamel paints over one coat of primer as per specification and instructions all Complete.	Sqm.	58.68			
18	MS Grill Providing, fabricating and installation all complete. MS Grill of 10x10mm solid core square rod @ 100c/c vertz. & 4 nos hortz. in 4.5x20mm MS Strip Frame (1 Sqm = 17.5 kg ) including cutting, welding etc. as per instruction of site engineer all complete	Sqm.	35.11			
19	cutting,welding & primer coat with needs size of specifecation Ms. Collapsible gate 4.5x20mm size 100 mm gap (27 kg/1cm2 ) all complete .	Sqm.	11.71			
20	Providing and laying Rubble Stone Masonry walls (wall height upto 5m) With 1:4 c/s Mortar including haulage upto 10m all complete as per instruction of site engineer all complete	cum.	3106.25			
21	Providing Concrete Railing at Front (2.5Ft, height, 3" diameter, white pintoed , reinforced concrete as per instruction of site engineer	Nos	58.0			

असीम माडारी  
इन्जिनियर

Bishnu Kumar Theguwa  
Chief Administrative Officer



Procurement Item Details

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
22	Pillar design work (Plaster Work 1:3 Painting Design Based on Drawing Provided in the front gate	LS	1.0			
23	Providing and laying Non-glazed tiles on the floor on 1:3 cement-sand plaster including grouting of joints with white cement all complete as per instruction of site engineer all complete	Sqm.	63.68			
24	Ghada (Reinforced concrete made height 2.5', Mid Diameter 1.5', Neck Circle 8" diameter, Designed and Painting as per instruction form Site Engineer .	Nos	16.0			
25	Supplying and Providing Armchair (C/C armrest center to center 22.8 inch, Overall depth 27.8 inch, Floor to seat height 16.3 inch, Floor to arm rest height 24 inch, Over back height 34.4 inch, Overall length of three seats 67.7 inch)	Nos	21.0			
26	Supplying and Providing Gamala Stand 4 gamala hold (MS Grill of 12x12mm solid core square rod in 4.5x20mm MS Strip Frame including cutting, welding etc.)	Nos	15.0			
27	Supplying and Providing Babboo Thunche(Garbage Bin) as per instruction of site engineer	Nos	80.0			
28	Providing and fitting HDP pipe with transportation all complete . Drainage Pipe 110 mm dia HDP pipes 4kg/cm2	R.M.	432.0			
29	Electrification Works for a single storey sanskritik Bhawan building	LS	1.0			
30	Water Supply and Sanitary Works for a single storey sanskritik Bhawan building	Ls	1.0			

*Sim*

असीम भण्डारी  
इन्जिनियर

*Bishnu Kumar Theguwa*

Bishnu Kumar Theguwa  
Chief Administrative Officer